Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work : Imrovements to Drain at Munikondappa Layout, Bagalagunte in Ward no. 14.

SNo	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Sri. J.C Ramachandra	
				In Figures (Rs)	In Words (Rs)
1	KSRRB 300-2 : Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH /Chapter 3 (Page No.142, Item No. 19.2)	Cum	222.75	126.55	Rupees One Hundred Twnty Six and Fifty Five Paisa Only
2	KSRB 4 - 1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.3)	Cum	37.13	5450.50	Rupees Five Thousad Four Hundred Fifty and Fifty Paisa Only
3	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No.KBS 4.6.2 (Page No.15, Item No. 4.31)	Sqm	720.00	328.13	Rupees Three Hundred Twnty Eighty and Thirteen Paisa Only
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. for TMT Bars Fe 500 Specification No.KBS 4.6.3 (Page No.17, Item No. 4.46.2)	Tonne	14.55	67873.17	Rupees Sixty SevernThousad Eight Hundred Seventy Three and Seventeen Paisa Only

Ramachandra

;nature of Contractor

Executive Enginee

Scanned by CamScanner

5	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M 20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum fine aggregates @ 0.459 cum, with superplastisiser @ 1 lts confirming to IS 9103 - 1999 Reaffirmed - 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery curing, complete as per specifications.Specification No.KBS 4.1, 4.6 (Page No.13, Item No. 4.11)	Cum	82.88	6731.66	Rupees Six Thousad Seven Hundred Thirty One and Sixty Six Paisa Only
6	KSRB 5.3-3 : Providing and constructing granite / trap/ basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing, complete as per specifications.KBS 5.1.13 (Page No.23, Item No. 5.9)	Cum	3.38	5609.53	Rupees Five Thousad Six Hundred and Nine and Fifty Three Paisa Only
7	concrete of mix 1:3:6 with OPC cement @ 220 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.2)	Cum	0.45	5650.96	Rupees Five Thousad Six Hundred and Fifty and Ninty Six Paisa Only
8	KSRB 15.1.3 : Providing ruled pointing to course stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (Page No..113, Item No. 15.3)	Sqm	7.50	109.75	Rupees One Hundred and Nine and Seventy Five Paisa Only
9	Supplying and fixing precast reinforced conceret slabs 10cm thick of mix M20 using 20mm and sownsize graded grantite metal using reinforecement 100mm dia steel at 150mm C/C both ways cost, transportation, hire charges of machinerym machine cuttng the vertical face to get plain even surface etc., complete with all lead and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	227.52	1793.94	Rupees One Thousad Seven Hundred Ninty Three and Ninty Four Paisa Only

Ramachandrea

;nature of Contractor

Executive Engineer

Scanned by CamScanner

10	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm (Page No.25, Item No. 5.29.1)	No.s	444.00	407.64	Rupees Four Hundred and Seven and Sixty Four Paisa Only
11	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. (Page No.122, Item No.15.80)	Sqm	90.00	29.12	Rupees Twenty Nine and Twelve Paisa Only
12	KSRB 15-19.2 : Providing and applying spary painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materiasl, labour, complete as per specifications. (Page No.122, Item No.15.81)	Sqm	90.00	73.91	Rupees Seventy Three and Ninety One Paisa Only
13	KSRRB 300-52.1 : Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications. MORTH specifications No.305.4.3 (Page No.148, Item No. 19.58)	Sqm	1260.00	22.40	Rupees Twenty Two and Fourty Paisa Only
14	KSRB 4 - 1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.3)	Cum	189.00	5450.50	Rupees Five Thousad Four Hundred Fifty and Fifty Fifty Paisa Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-57

Signature of Contractor

Executive Engineer

Scanned by CamScanner

15	Cement Concrete Pavement:- Construction un-reinforced plain cement concrete pavement, thickness as per design over a prepared sub base with OPC cement or any other type as per clause 1051.2.2. with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrance, sealant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grades as per drawing complete as per specifications. M20 (at 300 kg per cum coarse aggregate @ 0.64 cum and fine aggregate @ 0.43 cum) (Page No.177, Item No. 22.6.2)	Cum	189.00	5820.07	Rupees Five Thousad Eight Hundred Twenty and SevenPaisa Only
16	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift (Page No.178, Item No. 22.7)	Cum	1260.00	100.79	Rupees One Hundred and Seventy Nine Paisa Only
17	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement (Page No.178, Item No. 22.8.1)	Rmtr	275.00	128.79	Rupees One Hundred Twenty Eight and Seventy Nine Paisa Only
18	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4KM a) Basic rate for haulage of materials as per item No. 17.4/ KSRRB: M100-4,1 … Rs. 2.00 Tonne / Km b) Average earth of work 1.28 Tonne / Km Rs, 2.00 c) Add loading and unloading Page. No. 133 Item No. 17.1 PWD SR 2016-17	Cum	630.00	90.49	Rupees Ninty and Fourty Nine Paisa Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division

;nature of Contractor

Executive Engineer

Scanned by CamScanner